

Cranes operating in Rønne Harbour (near EKRN Bornholm/Rønne aerodrome)

This AIRAC AIP SUP 22/26 replaces AIRAC AIP SUP 03/26 on AIRAC 09 JUL 2026.

1 Introduction

From November 2025 to December 2028, several land based cranes extending from 193 FT MSL to 492 FT MSL, will be working in Rønne Harbour in periods of several months.

During the same period, several vessel based cranes extending from 400 FT MSL to 722 FT MSL will be working in Rønne Harbour in periods varying from several hours to several days.

All of these cranes penetrate the Inner Horizontal Surface and/or the Conical Surface and some will impact the instrument flight procedures at EKRN Bornholm/Rønne aerodrome.

To address this, three separate sets of instrument flight procedures have been established and these procedures will include additional instructions, guidelines, limitations or restrictions, to ensure the safe navigation of aircraft in the vicinity of the cranes.

These procedures can be found in the AIRAC SUP Differentiated instrument approach procedures to EKRN Bornholm/Rønne aerodrome.

ATC will notify aircraft which set of procedures are in use.

2 Temporary obstacles

Obstacles penetrating Obstacle Limitation Surfaces (OLS)						
OBST ID / Designation	OBST type	OBST position	ELEV (FT)	HGT AGL (FT)	Markings / Type, Colour	Remarks
Rønne Havn 1	Land based cranes	55 05 12.84N 014 41 34.11E	188	178	LIM F R	Permanent 01.12.2025 - 31.12.2026
Rønne Havn 2	Land based cranes	55 05 20.61N 014 41 34.38E	328	318	LIH F R	Permanent until 30.11.2026
Rønne Havn 3	Land based cranes Wind turbine parts	55 05 20.61N 014 41 34.38E	486	476	LIH F R	Permanent 01.01.2026 - 31.12.2028
Lone	Vessel crane	55 05 14.74N 014 41 27.46E	253	253	LIM FLG W	Temporary 01.12.2025 - 31.12.2026
Svanen	Vessel crane	55 05 14.74N 014 41 27.46E	401	401	LIH FLG W	Temporary 01.12.2025 - 31.12.2026
Aeolus	Vessel crane	55 05 14.74N 014 41 27.46E	607	607	LIH FLG W	Temporary 01.12.2025 - 31.12.2026
WIV Q Class	Vessel crane	55 05 14.74N 014 41 27.46E	640	640	LIH FLG W	Temporary 01.01.2027 - 31.12.2028
WIV P Class	Vessel crane	55 05 14.74N 014 41 27.46E	696	696	LIH FLG W	Temporary 01.01.2027 - 31.12.2028
Wind Mover	Vessel crane	55 05 14.74N 014 41 27.46E	717	717	LIH FLG W	Temporary 01.02.2026 - 30.11.2026

3 NOTAM

Further information will be published via NOTAM.

4 Completion of works

Completion of works is expected at the end of December 2028.

REF: AIP Denmark GEN 0.5, ENR 5.4 and AD 2 - EKRN.

Valid until further notice.